



QUOTE

QUOTE NO
6281

TO City of Blue Ridge
480 West First Street
Blue Ridge, GA 30513
Phone (706) 632-2091
Fax (706) 632-3278

VALID THRU	JOB SITE	DATE
2/14/2020	City of Blue Ridge--2020--	1/16/2020

DESCRIPTION	UNIT PRICE	EXTENDED
Widening and overlay of Depot Street from just below intersection with College Street to just before private gate at top of hill	0.00	0.00
Grading/excavation to build up shoulder/shift ditch line as needed for widening	2,000.00	2,000.00
Installation and Compaction of Base Material (build up shoulder for widening)	800.00	800.00
Installation and Compaction of 4" Asphalt (143 square yards, widen road by total of 6' prior to overlay, includes filling trench cuts as discussed)	48.95	6,999.85
Installation and Compaction of 1.5" F-Mix Asphalt (ovellay existing and widened areas, 547 square yards, includes tack coat)	12.71	6,952.37

TOTAL QUOTED PRICE: 16,752.22

* means item is non-taxable



QUOTE

QUOTE NO
6281

TO City of Blue Ridge
480 West First Street
Blue Ridge, GA 30513
Phone (706) 632-2091
Fax (706) 632-3278

<u>VALID THRU</u>	<u>JOB SITE</u>	<u>DATE</u>
2/14/2020	City of Blue Ridge--2020--	1/16/2020

The Following Notes Apply:

1. No erosion control costs are included.
2. No materials field testing costs are included.
3. No costs are included for the removal and replacement of any unsuitable or unstable soil materials if possibly encountered within the existing sub-grade area.
4. Johnson Paving, LLC assumes no responsibility for any possible settlement that may occur due to unsuitable or unstable subgrade or base material
5. No costs are included for any pavement edge or curb backfill and/or landscaping.
6. Final billing quantities will be calculated by the completed project measurements.
7. Asphaltic Concrete unit prices are as per current material quotation unit prices and are subject to possible change. Any possible increases would be due primarily to the continued volatility and the rising costs of asphalt bitumen and fuel used in the manufacture of all asphalt products.
8. All quantities quoted are based on averages. Asphalt thickness may vary throughout the project.

We propose to furnish all materials, labor and equipment in complete accordance with the above specifications and payment is to be made as invoiced. Please sign, date, and return within 30 days if the above bid is acceptable. We appreciate the opportunity to furnish this bid to you and look forward to a continued business relationship.

Yours truly,

JOHNSON PAVING, LLC

Earl W. Johnson

DATE OF ACCEPTANCE

PRINTED NAME

AUTHORIZED SIGNATURE

TRC Hauling & Paving, Inc. NEW

PO Box 2104
Blue Ridge, GA 30513

Estimate

Date	Estimate #
1/31/2020	176

Name / Address
City of Blue Ridge Rebecca Harkins 480 West First St Riverwood Subdivision Blue Ridge, Ga 30513

			Project
Description	Qty	Rate	Total
Depot Street - From college street up right side. widen 4-6' tap property line before gate. remove grass and dirt. add gravel base. compact pave 2" compacted asphalt From college street up to concrete driveway. widen 2'. remove grass & dirt. add gravel base. compact. pave 2" compacted asphalt - Patch area below college streets 2" compacted asphalt	1	5,570.00	5,570.00
Resurface from lower end of College Street to property line - clean. tac. pave 2" compacted asphalt	1	8,609.00	8,609.00
		Total	\$14,179.00